

ADDENDUM No. 3 TO THE CONTRACT DOCUMENTS

Project: Cells II-1 and II-2 Landfill Expansion Project V.2

Addendum Issue Date: June 24, 2014

Issued for Bid Date: May 27, 2014

Bid Due Date: July 1, 2014

Previous Addenda Issued: two

Issued By: Robert Lund, P.E.
City Engineer
City of Unalaska
rlund@ci.unalaska.ak.us
(907) 581-1260

This addendum is hereby made a part of the Request for Proposals Documents and modifies the original Request for Proposals Documents. The following corrections, changes, additions, deletions, revisions, and/or clarifications are hereby made a part of the contract documents for the Cells II-1 and II-2 Landfill Expansion Project V.2. In case of conflicts between this Addendum and previously issued documents, this Addendum shall take precedence. Bidders must acknowledge receipt of this addendum on the bid submitted.

ADDENDUM ITEMS

CONTRACT DOCUMENTS, SPECIFICATIONS AND DRAWINGS

Item 1:

Question from Bidder

Sheet M-203, Material List item 28, calls out a hose to connect between the enclosure and the side slope pumps. Please specify the requirements of this hose.

Answer: The hose is to be supplied by the pump manufacturer as part of the pump package. EPG Companies, Inc. uses a flexible PVC (Type SR) with polypropylene CamLock Fittings to permit a quick disconnection when servicing the pumps.

Item 2:

Question from Bidder

Sheet C-230, point 500, is called out in the Coordinate Tables (C-206) to be at elevation 6.5, which is lower than the elevation of the culvert that crosses Summer Bay Road. It appears that this area will hold open water, is that the intent?

Answer: Change point 500 to elevation 8.21. The intent is for storm water to flow from point 501 to point 500 to the culvert at point 422.

Item 3:

Question from Bidder

Addendum 1, Question 10: The answer to this question states that the use of the stockpile for use as Imported Fill is not allowed.

- a. Is it the intent to eliminate the note at the top of plan sheet C-204, which states that the stockpile is to be used for Import fill?*
- b. Is it allowable to use the stockpiled material if processed properly to meet the requirements of Import fill?*

Answer: Import Fill (re: 2.1 Materials, B. Import Fill) can be produced (screened) from the shot rock material if the rock is screened to 3-inch or less, and the number 200 component does not exceed 8% - as well as the other requirements for quality under 2.1.B are met. Otherwise, this material should be imported. All other materials provided under 2.1 Material shall be imported. The "Imported Fill" is intended to be used under the new Cells II-1 and II-2. The shot rock is to be used as general fill as depicted on Sheets C-230 and C-231; and the core of the new landfill berms. For clarity purposes, delete the word "Import" from the two general notes on the Cell Sections on Sheets C-204 and C-205 – located in the upper middle of the sections that point to the shot rock stockpile area.

END OF ADDENDUM NO. 3

No attachments